

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bowen of Pan American has this
date requested permission to plug the following described well:

Mr. Bowen guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name: Z.M. Hille Well No. 1

Location: SE NW Sec. 3 Twp. 32 Rge. 33 (E) (W)

County: Seward Total Depth 6000' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bowen was instructed to plug the well as follows:

8 5/8" to 659' circulated w/ cement. 5 1/2" to 5970' cemented.

Top perforations 4970' Plug bottom w/ bridge plug & 10 sacks cement.

Top of cement 4000' Mud 4000' to 1285'

Spot 25 sacks cement 1285' to 1200' Mud 1200' to 700'

Spot 50 sacks cement 700' to 550' Mud 550' to 60'

Plug, Hulls & 25 sacks cement 60' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent