

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

15-175-00245-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 6/56 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Helmerich & Payne, Inc. KCC LICENSE # 5293 ^{6/93}
(owner/company name) (operator's)

ADDRESS P.O. Box 558 CITY Garden City

STATE Kansas ZIP CODE 67846 CONTACT PHONE # (316) 276-3693

LEASE Prater WELL# 1 SEC. 28 T. 32^S R. 32 (East/West)

- - C -NE/4 SPOT LOCATION/QQQQ COUNTY Seward

1320 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
sk's not available

SURFACE CASING SIZE 8-5/8 SET AT 526 CEMENTED WITH Qntd to surface SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 2726 CEMENTED WITH Not available SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2610 to 2700 Open Hole 2726 to 2734

ELEVATION 2831 KB T.D. 2734 P.B.T.D. 2709 ANHYDRITE DEPTH 1620
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Well has 1 1/2" tbg stuck in hole with Glorietta sand. Top of 1 1/2" tbg at 2150'. Also has Glorietta csg leak @ 1189'. Workover to squeeze leak and fish 1 1/2" tbg has been unsuccessful. Has spent \$59000. Plug w/ 60/40 poz, 6% gel as per Glenn Barlows

(If additional space is needed attach separate page)

instructions. 20 sks @ 2150', 30 sks @ 1600', 30 sks @ 550', 5 sks @ 10', 125 sks down 4 1/2 x IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? _____

8-5/8 annulus.
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ken Jehlik PHONE# (316) 276-3693

ADDRESS P.O. Box 558 City/State Garden City, Kansas

PLUGGING CONTRACTOR Halliburton KCC LICENSE # _____
(company name) (contactor's)

ADDRESS Liberal, Kansas PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-15-93 AUTHORIZED OPERATOR/AGENT: Ken Jehlik
(signature)

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1993
CONSERVATION DIVISION
Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 20, 1993

Helmerich & Payne, Inc.
P.O. Box 558
Garden City, KS 67846

Prater
API N/A
1320 FNL 1320 FEL
SEC. 28-32S-32W
Seward County

Dear Mr. Ken Jehlik,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760