

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1983

COUNTY Sumner SEC. CONSERVATION DIVISION TWP. 30s RGE. 3w E/W  
Location as in quarters or footage From 1/4 Division  
Wichita, Kansas  
C SE NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Dunne-Gardner Petroleum, Inc.  
Lease Name Fullmer #1 Well No. \_\_\_\_\_  
Office Address 200 W. Douglas, Suite 250, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 8/1/83  
Plugging completed 8/12/83  
Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Kirkpatrick  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4315'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	252'	none
				5 1/2"	4310'	2032'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Tagged bottom @ 2860'. Lost bailer in hole. Plugged off bottom with 6 sacks  
cement, pushed plug & dumped 4 more sacks cement. Shot & worked pipe at 2650',  
2467', & 2032'. Pulled pipe out to 1100', spotted 35 sacks common cement,  
pulled pipe out to 355', circulated cement with 100 sacks cement to surface,  
finished pulling pipe.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing PULLING

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of Aug, 1983



Irene Hoover  
Notary Public.

My Commission expires: \_\_\_\_\_