

15-191-01490-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

SUMNER COUNTY, KS County. Sec. 2 Twp. 30S Rge. 4W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner K & E AND BRADLEY
Lease Name HALL 'B' Well No. 1
Office Address 719 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 18th, 1958 19
Application for plugging filed 11-18-58 19
Application for plugging approved 11-18-58 19
Plugging commenced 11-18-58 19
Plugging completed 11-18-58 19
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well unknown
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4400' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	299'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 240' set solid plug
with 15 sx of cement. Filled with heavy mud
to 40' set solid bridge with 10 sx cement to
base of cellar.
Job complete 11-18-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DALE SILCOTT (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1958

My commission expires August 11th, 1962.

Patricia M. Edwards,
Notary Public.

PLUGGING
FILE SEC. 2 T 30 R 4W
BOOK PAGE 146 LINE 25

NOV 22 1958
11-22-58
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

OPERATOR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	FARM:	#1 HALL 'B'
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	LOCATION:	SW SW SE Sec. 2-30S-4W Sumner Co, Kansas
CASING:	8-5/8" @ 299' (225 ft)	COMMENCED:	11-5-58
R.T.D.	4400'	COMPLETED:	11-18-58
		ELEVATION:	1385' KB
		PRODUCTION:	D & A

FORMATION RECORD

Depths shown indicate bottom of formations.

Sand	35
Shale & Shells	760
Lime & Shale	2990
Shale & Sand	3170
Lime & Shale	3250
Shale	3338
Lime	3540
Lime & Shale	3786
Lime	3870
Lime & Shale	3955
Shale & Chert	3968
Chert	3994
Lime	4300
Lime & Shale	4325
Shale	4400
R.T.D.	4400

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a correct and true copy of the Driller's Log of the #1 HALL 'B' well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 20th day of November, 1958.

[Signature]
Notary Public

My commission expires: August 11th, 1962.

NOV 22 1958

PLUGGING

FILE SEC. 2 T. 30 R. 46
BOOK PAGE 146 LINE 25

CONSERVATION DIVISION
Wichita, Kansas