


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County. Sec. 29 Twp. 30S Rge. 5 (E) 5 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW&SW&SE" or footage from lines _____
Lease Owner MULL DRILLING COMPANY, INC.
Lease Name TCNN Well No. "A"-1
Office Address 1625 WICHITA PLAZA, WICHITA, KANSAS 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 1 NOV 19 66
Application for plugging filed 1 NOV 19 66
Application for plugging approved 1 NOV 19 66
Plugging commenced 1 NOV 19 66
Plugging completed 1 NOV 19 66
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production NONE 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING

Producing formation NONE Depth to top _____ Bottom _____ Total Depth of Well 4582'RB Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SURFACE HOLE</u>	<u>WATER</u>	<u>SURFACE</u>	<u>248'RB</u>	<u>8 5/8"OD</u>	<u>240.05'</u>	<u>LEFT IN</u>
<u>(SEE ATTACHED LOG)</u>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY DRILLING MUD TO 240', SET PLUG, PUT IN 2 SACKS DRY CEMENT, 1/2 SACK HULLS AND CEMENTED WITH 25 SACKS CEMENT, FILLED HOLE WITH DRILLING MUD TO 35', SET PLUG, PUT IN 2 SACKS DRY CEMENT AND 1/2 SACK HULLS AND CEMENTED WITH 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor DONELSON DRILLING COMPANY
Address 212 DERBY BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
212 DERBY BUILDING, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of NOVEMBER, 19 66

My commission expires 28 JULY 1967 MARY BAILY Notary Public.

15-095-30254-0000

"A" - 1 TONN
MULL DRILLING COMPANY, INC.

Elevation 1373 RB
-1368 GL

TOTAL DEPTH: 4582' RB
CONTRACTOR: Donelson Drilling Co.
COMMENCED: 10-21-66
COMPLETED: 11-1-66
INITIAL PROD.: D&A

Location: Center SW SW
Section: 29-30S-5W
Kingman County, Kansas
Casing Record:
8 5/8" OD Set at 248' RB W/ 210 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	248'
Shale	1002'
Shale & Lime Shell	1310'
Lime	1325'
Lime & Shale	1795'
Lime	1800'
Shale & Lime	1905'
Sandy Shale W/Lime Strks.	2050'
Shale & Lime	2405'
Lime & Shale	3220'
Shale	3355'
Lime	3410'
Shale	3516'
Lime - Kansas City	3736'
Lime & Shale	4122'
Lime - Chert - Mississippi	4454'
Shale & Lime	4556'
Lime - Viola - R.T.D.	4582'

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1966

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Donelson Drilling Company

By James L. Donelson
James L. Donelson

STATE OF KANSAS
COUNTY OF SEDGWICK, SS.

Subscribed and sworn to before me, a Notary Public, this 2nd day of November, 1966.

Marilyn J. Snyder
Marilyn J. Snyder

My commission expires: May 7, 1969.