

15-095-21551-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21,551

LEASE NAME Bogle

WELL NUMBER 2-25 SWD

 Ft. from S Section Line

 Ft. from E Section Line
 NE NE NW

SEC. 25 TWP. 30 RGE. 5W (E) or (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 8-2-88

Plugging Completed 8-25-88

LEASE OPERATOR W.L. Kirkman, Inc.

ADDRESS P.O. Box 782290
Wichita, Kansas 67278-2290

PHONE # (316) 685-5372 OPERATORS LICENSE NO. 5673

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	241'	none
				4-1/2"	3684'	3122'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3300' and 4 sacks cement. Shot pipe @ 3303', 3122', pulled a total of 74 joints of 4-1/2" casing. Plugged surface with 200# hulls, 10 sacks gel and 125 sacks cement, 60/40 pos, 2% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SEP - 6 1988

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19 88

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:

Irene Hoover
Notary Public

