


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 1 Twp. 30S Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines. NW NW NE
Lease Owner. Atlas Minerals, Division of Atlas Corp.
Lease Name Billau Well No. 1
Office Address 707 Nat'l Bank of Tulsa Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 7, 19 69
Application for plugging filed February 7, 19 69
Application for plugging approved February 7, 19 69
Plugging commenced February 7, 19 69
Plugging completed February 7, 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Ralph Warren of Pratt)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4533 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	254'	8-5/8"	1/29/69	-----
	Casing					

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 250 Feet;
1/2 sax Hulls, Plug and 25 sax Cement thru
the Drill Pipe; Mud to 40 Feet; 1/2 sax
Hulls, Plug bridged w/Kelly and 10 sax
Cement to Base of Cellar; 2 sax Cement
in Rat Hole. Job Completed @ 2:15 P.M.
on 2/7/69.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Bldg., Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas (Address)

Subscribed and Sworn to before me this 10th day of February, 19 69

Louise K. Whitted - Notary Public.



My commission expires November 26, 1970.

DRILLERS LOG

BILLAU NO. 1

CASING RECORD:	OPERATOR:	Atlas Minerals, Division of Atlas Corporation	DESCRIPTION:
8-5/8" @ 254' w/225 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	NW NW NE Sec. 1-30S-6W Kingman County, Kansas
TOTAL DEPTH:	COMMENCED:	January 29, 1969	
4533'	COMPLETED:	February 7, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	255	
Red Bed & Shale	255	1245	
Lime & Shale	1245	2080	
Shale & Lime	2080	2520	
Lime & Shale	2520	3365	
Lime	3365	3944	
Lime & Shale	3944	4100	
Lime & Chert	4100	4365	
Lime & Shale	4365	4533	D&A

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 10th day of February, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.