


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 4 Twp. 30 Rge. 6 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Morgenstern & Specter, Inc.
Lease Name Ravenstein Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-8-54 19
Application for plugging filed January 30, 1961 19
Application for plugging approved January 31, 1961 19
Plugging commenced 2-6-61 19
Plugging completed 2-9-61 19
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation Kansas City Depth to top 3503 Bottom 4072' Total Depth of Well 4685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	168'	None
				5-1/2"	4170'	3283'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4120', sanded from 4120' to 3500' and dumped 4 sacks of cement @ 3500' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 250', set 10' rock bride to 240' and ran 15 sacks of cement @ 240'. Mudded to 160' set 10' rock bridge to 150' and ran 10 sacks of cement @ 150'. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1961
3-10-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of February, 1961

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



15-095-00396-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company: M. B. ARMER
Farm: Ravenstein No. 1

SEC. 4 T. 30 R. 6W
NE NW NW

Total Depth. 4685
Comm. 4-18-54 Comp. 5-8-54
Shot or Treated.
Contractor. Armer, Inc.
Issued. 4-2-55

County Kingman
KANSAS



Elevation. 1461 KB

Production. 26 BO / 65% wtr

CASING:

8" 167'	
5" 4170'	
shale & shells	167
redrock, shale & shells	460
shale, shells & salt	1015
shale & shells	1272
shale & lime	1480
lime	1595
shale & lime	1910
shale & shells	2340
shale & lime	2820
broken lime	2950
shale & lime	3450
broken lime	3530
lime	3840
lime & shale	4075
shale	4078
chert lime	4098
lime	4220
chert lime	4248
lime	4305
lime & shale	4370
shale	4445
lime	4470
chert lime & shale	
sand	4520
lime & sand	4545
shale sand	4572
lime	4685
Total depth	
Tops: (K.B. Meas.)	
Douglas	3019
Lansing	3226
Kansas City	3503
Mississippi	4073
Viola	4457
Simpson	4479
Arbuckle	4590

Figures Indicate Bottom of Formations.