


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 4 Twp. 30 Rge. 6 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW NE NW
Lease Owner Morgenstern & Spceter, Inc.
Lease Name Ravenstein Well No. 3
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 7-11-56 19____
Application for plugging filed Jan. 30, 1961 19____
Application for plugging approved Jan. 31, 1961 19____
Plugging commenced 1-26-61 19____
Plugging completed 2-3-61 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample.
Producing formation Kansas City Depth to top 3501 Bottom 3729 Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				XXXX		
				10-3/4"	160'	None
				7"	3729'	2721'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3730', ran sand from 3730' to 3700' and dumped 4 sacks of cement @ 3700'. Pulled 7" casing. Bailed fluid to 260', set 10' rock bridge to 250' and ran 15 sacks of cement. Mudded to 155' set 10' rock bridge to 145' and ran 10 sacks of cement. Mudded to 30' and ran 20 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1961

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knicht Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of February, 1961

My commission expires May 20, 1964 Milton J. Volin Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


15-095-01300-0000

Company- McKNAB & LINDSAY ET AL
 Farm- Ravenstein No. 3

SEC. 1 T. 30 R. 6N
 SW NE NW

Total Depth. 3730'
 Comm. 6-28-56 Comp. 7-11-56
 Shot or Treated.
 Contractor. McKnab & Lindsay
 Issued. 11-17-56

County Magman
 KANSAS



Elevation. 1163' RB

Production. SWDW

CASING:

10 3/4" 160' w/125 sx cem.
 7" 3729' w/125 sx cem.

Figures Indicate Bottom of Formations

shale-sand	180
shale	1120
shale-lime	1575
lime-chert-shale	1685
lime-shale	1840
lime	1965
shale-lime	2190
sand-shale	2215
shale-lime	2250
sand-shale	2320
lime-shale	3065
lime	3213
lime-shale	3238
Core #1	3263
lime	3345
lime-shale	3519
Core #2	3533
lime	3553
Core #3	3583
lime	3685
Core #4	3715
lime	3730
Total Depth	

TOPS:Scout	
Lansing	3223
Kansas City	3501