

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

XX4
API NUMBER 15-063-21,224-00-00

LEASE NAME Coberly "D"

WELL NUMBER 1-19

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 19 TWP. 15S RGE. 28 (X) or (W)

COUNTY GOVE

Date Well Completed 9-23-88

Plugging Commenced 9-23-88 2:00 AM

Plugging Completed 9-23-88 4:00 AM

9-23-88 (date)

LEASE OPERATOR Landmark Oil Exploration & Davis Petroleum

ADDRESS 250 N. Water, Suite 308 Wichita, Kansas 67202

PHONE#(316) 265-8181 OPERATORS LICENSE NO. 06113

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on

by Gilbert Scheck Dist IV (KCC District Agent's Name).

Is ACO-1 filled? by operator If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Surface	8 5/8"	0	272'	8 5/8"	272	none 9-30-88
						CONSERVATION DIVISION
						Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

20 sx. 60/40 Pozmix, 6% Gel @ 1900', 100 sx. 60/40 Poz 6% gel @ 900' W/1 sack flo-seal,
40 sx. 60/40 Poz. 6% Gel @ 325', 10 sx. 60/40 Poz 6% Gel @ 40', 10 sx. in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Services License No.

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Oil Exploration


STATE OF Kansas COUNTY OF Barton ss.

Greg Davidson (Employee of Operator) or (xxxxxx) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1988



My Commission Expires: 5-20-89

Bessie M. DeWerff
Bessie M. DeWerff
Notary Public

15-03-21224-00-00

DRILLERS WELL LOG

DATE COMMENCED: September 14, 1988
DATE COMPLETED: September 23, 1988

Landmark Oil Exploration & Davis Pet. Inc
COBERLY "D" 1-19
SE SE SE Sec. 19-15S-28W
Gove County, Kansas

0 - 760 Sand & Shale
760 - 1425 Shells & Shale
1425 - 1906 Shale
1906 - 1939 Anhy
1939 - 4350 Lime & Shale
4350 R.T.D.

Elevation: 2484 GR 2489 KB

FORMATION DATA

Sample Tops:
Anhydrite 1906'
Base Anhydrite 1939'
Heebner 3610'
Toronto 3630'
Lansing 3647'
Stark 3900'
B K/C 3975'
Marmaton 4000'
Ft. Scott 4169'
Cherokee Shale 4196'
B. Johnson 4254'
Mississippi
T.D. 4350'

SURFACE CASING:

8 5/8" Set at 272' W/180 sx. 60/40
Pozmix, 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS SS
COUNTY OF BARTON

Greg Davidson of lawful age, does swear and state that the facts and statements
herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 27th day of September 1988.

My Commission Expires: 5-20-89

Bessie M. DeWerff
Bessie M. DeWerff, Notary Public

