

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pratt County, Sec. 6 Twp. 28 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Graham-Messman-Rinehart Oil Company

Lease Name Bucklin Well No. 1

Office Address 1005 E. Second Street, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry - lost hole, rig skidded 50 ft. west

Date well completed November 7, 19 53

Application for plugging filed November 7, 19 53

Application for plugging approved November 7, 19 53

Plugging commenced November 7, 19 53

Plugging completed November 7, 19 53

Reason for abandonment of well or producing formation Lost hole - skidded rig

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 148, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3037 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 300 ft. with
1/2 sk. hulls and 30 sx. cement.
Cemented through drill pipe.
Top plug at 40 ft. with 1/2 sk.
hulls and 10 sx. cement. Mud
to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Oil Company

Address 1005 E. Second St., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland

1005 E. Second St., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 53

My commission expires December 1, 1956

RECEIVED
Notary Public.

24-2675-5 2-52-20M

PLUGGING
FILE SEC 6 T 28 R 11 W
BOOK PAGE 44 LINE 24

NOV 19 11-A-53
CONSERVATION DIVISION
Wichita, Kansas

#1 BUCKLIN

WELL RECORD

Location: SE SE NE, Sec. 6-28-11W
Pratt County, Kansas
Operator: Graham-Messman-Rinehart Oil Company
1005 E. Second St., Wichita, Kansas
Contractor: Graham-Messman-Rinehart Oil Co.
1005 E. Second St., Wichita, Kansas
Commenced: October 30, 1953
Completed: November 7, 1953
Production: Lost Hole -
skidded rig
Casing Record: 8 5/8" at 250 ft. w/250 sx. cem.

LOG

Sand & Gravel	155
Shale	537
Shale	907
Shale	1030
Shale	1543
Shale - Lime	1745
Shale - Shells	1875
Shale - Lime	2060
Shale - Lime	2155
Lime - Shale	2325
Lime - Shale	2369
Shale - Lime	2520
Shale	2730
Shale - Lime	2865
Shale - Lime	2974
Shale	2985
Shale	3037 T.D.

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this
17th day of November, 1953.

Barbara J. Scott
Notary Public

My commission expires: December 1, 1956.

PLUGGING
FILE SEC 6 T 28 R 11W
BOOK PAGE 141 LINE 24

RECEIVED
STATE COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS