


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

PRATT County, Sec. 16 Twp. 27 Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner National Cooperative Refinery Ass'n
Lease Name Lemon Well No. 1
Office Address Rule Bldg., Wichita 2, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/12 19 56
Application for plugging filed 9/12 - verbally 19 56
Application for plugging approved 9/12 - verbally 19 56
Plugging commenced 9/12 19 56
Plugging completed 9/12 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4832 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	323'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

#1 plug @ 300', 1/4 sack hulls and 20 sacks cement. through
drill pipe. #2 plug @ 35', 1/4 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL
Harold Wurst (employee of drilling contractor or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 56

My commission expires 6/17/58 Clara L. Lumm Notary Public.

PLUGGING
FILE SEC 16 T. 27 R. 15W
BOOK PAGE 98 LINE 41

09-18-56
WICHITA, KANSAS

National Cooperative Refinery Ass'n
Lemon #1

NW NW SE Sec. 16-27-15W
Pratt County, Kansas

R.T.D. 4832

Casing Record
8 5/8" Set @ 323' w/1.75 sx cmt.

Commenced 8/22/56
Completed 9/12/56

Contractor: Bennett & Roberts Drilling Co.

----- Figures Indicate Bottom of Formation -----

Surface Sand	45'
Sand & Clay	190
Sand & Shale	240
Gray Shale	280
Red Bed	990
Anhydrite	1012
Red Bed	1490
Shale & Lime Streaks	1855
Shale & Lime	2075
Lime	2305
Lime & Shale	2820
Shale	2906
Shale & Lime	3205
Lime	3275
Lime & Shale	3540
Lime	3640
Lime & Shale	3715
Lime	3905
Lime & Shale	4000
Lime	4490
Sand & Mississippi	4520
Lime & Chert	4561
Lime	4611
Lime, Shale, Viola	4637
Viola	4692
Simpson Shale	4741
Simpson	4797
Arbuckle	4832

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By Eus Baker

Subscribed and sworn to before me this 17th day of September, 1956.

Clara [Signature]
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC. 16 T. 27 R. 15W
BOOK PAGE 98 LINE 41