


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

**WELL PLUGGING RECORD**

Pratt County, Sec. 15 Twp. 27 Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Braden Drilling Co.  
Lease Name Earlywine Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7-28-60 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8-3-60 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4606 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	400	None
				5-1/2"	4597	3996'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 50 sacks of cement to 4340' and killed gas. Pulled 5 1/2" casing. Checked fluid to 40', bailed fluid to 300' and set 10' rock bridge to 290'. Ran 20 sacks of cement, mudded hole to 35', set 5' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED.

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 10 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1960

Milton J. Volin  
Notary Public.

My commission expires 5-20-64



DRILLER'S LOG

R

Braden Drilling, Inc. et al  
EARLYWINE #1 15-27-15W  
NE/4 SE/4 NW/4 Sec. 13-27-15W  
Pratt County, Kansas

Commenced: December 8, 1959

Completed: December 24, 1959

Ran 349 ft. of 8 5/8" surface casing  
and cemented with 325 sacks cement.

Ran 4599.65' 5 1/2" oil string. Set at  
4590.03' and cemented with 100 sacks  
cement.

Sand and gravel	155 ft.
Shale	175
Sand	200
Lime and shale with sand streaks	345
Redrock shale and shells	1000
Shale	1015
Anhydrite	1030
Shale	1300
Shale and shells	1830
Shale and lime	2000
Lime	3045
Lime and shale with sand streaks	3160
Lime	3180
Lime and shale	3278
Lime	3440
Lime and chalk Lime	3540
Lime	3655
Lime and shale	3810
Lime	3910
Shale and Lime	3984
Lime (Brown)	4005
Lime	4100
Lime Cherty	4137
Lime	4491
Sand	4511
Lime and Chert	4530
Lime and Chert	4561
Lime	4597 Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

AUG 1 1960

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct log of the above  
captioned well, as shown by the daily drilling reports.

BRADEN DRILLING, INC.

By *F. M. Callaway*  
F. M. Callaway

Subscribed and sworn to before me this 30th day of December, 1959.

My commission expires: March 21, 1962

*Helen Schultz*  
Helen Schultz, Notary Public

R

DRILLER'S LOG

Braden Drilling, Inc. et al  
EARLYWINE #1  
NE/4 SE/4 NW/4 Sec. 15-27-15W  
Pratt County, Kansas

Commenced: December 9, 1959  
Completed: December 23, 1959

Set 349 ft of 8 5/8" and cemented  
with 325 sacks cement.

Set 4590 ft of 5-1/2" and cemented  
with 100 sacks cement.

Sand and Gravel	155 ft.
Shale	175
Sand	200
Lime and shale	345
Red rock, shale and shells	1000
Shale	1015
Anhydrite	1030
Shale	1300
Shale and shells	1830
Shale and lime	2000
Lime	3045
Lime & shale with sand streaks	3160
Lime	3180
Lime and shale	3278
Lime	3440
Lime and chalk lime	3540
Lime	3655
Lime and shale	3810
Lime	3910
Shale and lime	3984
Lime	4100
Lime cherty	4137
Lime	4491
Sand	4511
Lime and Chat	4530
Lime and chert	4561
Lime	4597 Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1960  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct log of the above  
captioned well, as shown by the daily drilling reports.

BRADEN DRILLING, INC.

By *J. L. ...*

Subscribed and sworn to before me this 9th day of August, 1960.

*Helen Schultz*  
Helen Schultz, Notary Public

My commission expires March 21, 1962