


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt County. Sec. 15 Twp. 27 Rge. 15 (E) W(W)  
Location as "NE/CNW/SW" or footage from lines NE SE SW  
Lease Owner Prime Drilling Company  
Lease Name Earlywine Well No. 1  
Office Address 814 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 30 19 58  
Application for plugging filed December 30 19 58  
Application for plugging approved December 30 19 58  
Plugging commenced December 30 19 58  
Plugging completed December 31 19 58  
Reason for abandonment of well or producing formation no oil and/or gas in commercial quantities found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4545 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	305'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 240'. Set Plug #1 at 240' with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' cemented with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 7 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Prime Drilling Company  
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol  
814 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of January, 19 59

Darlene May  
Darlene May Notary Public.



PLUGGING  
FILE SEC. 15 T. 27 R. 15W  
BOOK PAGE 10 LINE 1

ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company  
 NE SE SW Sec. 15-27S-15W,  
 Pratt County, Kansas  
 EARLYWINE NO. 1

CONTRACTOR: Prime Drilling Company  
 COMM: 12-16-58  
 COMP: 12-31-58

Remarks: Set 8-5/8" surface casing  
 at 305' cemented with 250  
 sacks cement.

Formations:

Top Soil & Clay	30'
Sand	100'
Sand & Shale	307'
Sand, Shale & Red Bed	815'
Red Bed & Shale	1270'
Anhydrite	1030'
Shale & Shells	1980'
Lime & Shale	2325'
Shale & Limw W/Sand Streaks	2410'
Lime & Shale	2595'
Sandy Shale & Lime	2665'
Lime & Shale	2920'
Shale & Lime w/Sand	3045'
Lime & Shale	3255'
Lime w/Shale	3335'
Lime & Shale	3415'
Lime	3820'
Lime w/Sand & Shale	3945'
Lime	4470'
Lime & Sand	4490'
Lime, Sand Chert	4505'
Sand	4515'
Sand w/Lime	4541'
Cherty Lime	4545'
Rotary Total Depth (D&A)	4545'

We certify the above log is true and  
 correct to the best of our knowledge  
 and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*

R. R. McNicol

RECEIVED  
 STATE CORPORATION

JAN 7 1959

COM. STATE OF KANSAS  
 WASHINGTON, D. C.

PLUGGING  
 FILE SEC 15 T 27 R 15W  
 BOOK PAGE 10 LINE 1