

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,126-00-0

LEASE NAME Green

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 6 TWP. 28 RGE. 12W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 5-9-97

Plugging Completed 5-13-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P. O. Box 783188 Wichita, KS 67278-3188

PHONE: (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4441'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1771'	none
				4 1/2	3855'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s' Sanded off bottom to 3660' & ran 4 sks cement. Shot well at 2691', pipe came loose. Pulled pipe to 1800', pumped 50 sks cement. Displaced w/gel. Pulled pipe to 400', pumped 50 sks cem. Pulled up to 40', pumped 10 sks cement. Pulled rest of pipe. Tied on to annulus. Mix & pump 110 sks cement. Shut in. 60/40 6%. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1997

[Signature]
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORP
MAY 21 1997