


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County. Sec. 5 Twp. 28S Rge. 23W (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Continental Oil Company
Lease Name J. Becker Well No. 1
Office Address Box 267, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed March 16 1964
Application for plugging filed March 16 1964
Application for plugging approved March 16 1964
Plugging commenced March 16 1964
Plugging completed March 16 1964
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampe
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4511 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	257'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 250' w/40 sx.
Set top plug @ 40' cemented
with 20 sx cement. Cemented
rathole with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1964

Jean Hollar
Notary Public.

My commission expires 5-22-66

State
File

DRILLERS LOG

J. Becker No. 1

CASING RECORD: 13 3/8" @ 257' w/250 sx cement
 COMPANY: Continental Oil Co.
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: February 28, 1964
 TOTAL DEPTH: 4511' COMPLETED: March 16, 1964
 DESCRIPTION: SE NW SE 5-28S-12W Pratt Co., Kans.
 ELEVATION: 1794 DF 1707 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	65	
Shale	65	100	
Shale & Redbed & Shells	100	1020	
Shale & Lime	1020	1695	
Lime Shale & Salt	1695	1820	
Lime & Shale	1820	2010	
Lime	2010	2195	
Shale & Lime	2195	2705	
Shale	2705	2822	
Lime	2822	2850	
Shale & Lime	2850	3665	
Lime	3665	4182	
Chert	4182	4189	
Lime	4189	4200	
Lime & Chert	4200	4273	
Lime	4273	4357	
Lime & Chert	4357	4433	
Lime & Shale	4433	4490	
Arbuckle	4490	4511	

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1964

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 17th day of March, 1964.

John Hollan
Notary Public

My Commission Expires:

5-22-66

RECEIVED
STATE CORPORATION COMMISSION
MARCH 20 1964
WICHITA, KANSAS

State