


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 2 Twp. 28 Rge. (E) 12(W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Pickrell Drilling Company

Lease Name Thomas Well No. 1

Office Address 705 4th Natl Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October ~~September~~ 9, 1963

Application for plugging filed October ~~September~~ 9, 1963

Application for plugging approved October ~~September~~ 9, 1963

Plugging commenced October ~~September~~ 9, 1963

Plugging completed October ~~September~~ 9, 1963

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4410 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 250 feet. Set plug. Cemented with
40 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 20 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

10-15-63

OCT 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY

Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Carl W. Sebitts

(Employer, owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

C. W. Sebitts
705 4th National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 14th day of October, 1963

Maxine Blackman
Notary Public.

My commission expires June 21, 1966



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
 705 4th National Bank Bldg.
 Wichita, Kansas
 LOCATION: Thomas No. 1 - C SW NW 2-28-12W,
 Pratt County, Kansas

Rotary Drilling Commenced 9-24-63
 Rotary Drilling Completed 10-9-63

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: (7 jts) 8 5/8" surface casing set at 276', cemented with 300 sacks cement. Circulated. Completed 11:00 P.M. September 24, 1963. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

175	Sand	
230	Red Bed	
255	Red Bed & Gravel	C.F.S.
760	Red Bed	3707
1550	Shale & Shells	3770
1700	Shale & Lime	3780
2045	Lime	3805
3657	Lime & Shale	3841
4105	Lime	3880
4204	Mississippian	3935
4300	Mississippian-Kinderhook	4115
4315	Kinderhook	4125
4330	Viola Chert	4135
4404	Viola	4300
4410	Simpson	4305
4410	RTD	4315
		4325
		4330
		4350
		4400
		4406
		4410

Slope Tests

2500
 3000
 3500
 4000

S.L.M.

3657
 4135
 4357

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 15 1963
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 14th day of October, 19 63, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Maxine Blackman, Notary Public