

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-22442-00-00

LEASE NAME HJV BRECHEISEN "A"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

660 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 31 TWP. 34S RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 07-03-2003

Plugging Commenced 07-04-2003

Plugging Completed 07-04-2003

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S. TAYLOR ST., SUITE 400, AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-03-2003 (date)

by DODGE CITY OFFICE (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1803	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. TIH W/4-1/2" DP TO 3250'. SPOT 100 SXS 60/40 POZ W/6%GEL @ 3250. TOH TO 1840' & SPOT 50 SXS. TOH TO 700' & SPOT 40 SXS. TOH TO 40' & SPOT 10 SXS AT 0-40'. SPOT 15 SXS IN RH & 10 SXS IN MH. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P. O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey

(Address) 701 S. TAYLOR, SUITE 400, AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 29 day of July, 2003



Lori Pearson
Notary Public

Expires: 2/28/05