

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20, 620-  
0000  
LEASE NAME Lightcap

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
1320 Ft. from S Section Line  
200 Ft. from E Section Line

LEASE OPERATOR Dorchester Hugoton, Ltd.  
ADDRESS 9696 Skillman Suite 320 LB 42 Dallas, TX  
75243-8200

SEC. 34 TWP. 34S RGE. 39W (E) or (W)  
COUNTY Stevens

PHONE# (214) 739-2002 OPERATORS LICENSE NO. #09736

Date Well Completed 12/22/82  
5/24/88

Character of Well Gas

Plugging Commenced

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/24/88

The plugging proposal was approved on May 11, 1988 (date)

by Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Council Grove Depth to Top 2987 Bottom 3219 T.D. 3335

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Council Grove</u>	<u>Gas</u>	<u>2987</u>	<u>3219</u>	<u>8 5/8</u>	<u>592</u>	<u>-0-</u>
				<u>5 1/2</u>	<u>3327</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 280' Cement/Halliburton Light Class H Mixed at 13.1 lbs/gal. yield of 1.89 CF/Sack mixed with 4 sacks cotton seed hulls, 4 BBLs water and 75 BBLs Slurry down 5 1/2" from surface down to 3150 feet. Pumped 20 sacks cement down Annulus between 8 5/8-5 1/2

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A

Address P.O. Box 1598 Liberal, KS 67901

STATE OF Kansas COUNTY OF Stevens, ss.

Johnny L. Booth

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Johnny L. Booth

(Address) 9696 Skillman Suite 320 LB 32 Dallas, TX 75243-8200

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 88

JUN 2 1988

My Commission Expires 6/26/89  
Wichita, Kansas  
Notary Public