


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Morton County. Sec. 33 Twp. 34 Rge. 39 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines C- NE/4
Lease Owner Kuhn Bros
Lease Name Kendall Well No. 1
Office Address 726 Union Center, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 5-26 1937
Application for plugging filed 1-17 1961
Application for plugging approved 1-17 1961
Plugging commenced 2-16 1961
Plugging completed 2-16 1961
Reason for abandonment of well or producing formation New well was drilled
on this unit to replace the old well.
If a producing well is abandoned, date of last production 1-19 1961
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Chase Depth to top 2610' Bottom 2744' Total Depth of Well 2744' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	gas	2610	2630	6 $\frac{1}{4}$	5 $\frac{1}{2}$ liner	none
Krider	gas	2640	2688	6 $\frac{1}{4}$	5 $\frac{1}{2}$ liner	none
Winfield	gas	2700	2744	6 $\frac{1}{2}$	5 $\frac{1}{2}$ liner	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2744 to 2570' 50 sacks of cement by Halliburton

2570 to 2569 Rubber Halliburton Plug.

2569 to 2375 50 sacks of cement by Halliburton.

2375 to 20' Mud

20 to 19' Halliburton Plug

19' to 4' Cement.

Casing was cut off and a cap was welded on

7" and the 10-3/4" NO CASING WAS PULLED FROM THIS WELL.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oilwell Cementing Co.
Address Duncan, Okla.

STATE OF Kansas, COUNTY OF Stevens, ss.
M. L. Dale (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. L. Dale

Box 1166, Hugoton, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February 19 61

Shirley D. Bradley Caudell
Notary Public.

My commission expires November 8, 1964

FILED
STATE CORPORATION COMMISSION

FEB 27 1961

CONSERVATION DIVISION

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

KUHN BROS.
~~Walker~~ No. 1
Randall

SEC. 33 T. 34 R. 39W.
Center NE

Total Depth. 2744
Comm. 2-19-37 Comp. 5-26-37
Shot or Treated.
Contractor.
Issued. 3-12-38

County Morton.



CASING.

7" 2575'

Elevation.

Production. 8,932,000 G.
R.P. 414 #.

Figures Indicate Bottom of Formations.

No log to	2590
limo	2630
shale blue	2633
limo	2640
shells and shale	2675
sand and limo	2688
red bed	2700
limo	2712
shale	2717
sdv limo	2720
shale grey	2735
limo hard	2740
sdv limo	2744

Total Depth.

PRODUCTION RECORD.

2620 1st show gas.
2635 2nd show gas
2660 3rd gas 1,500
2675-2688 4th gas
2700-2712 5th gas
2717-2720 6th gas O.F. 4,500
2658-2724 shot with 110 qts.
Increase O.F. 8,932

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1961
CONSERVATION DIVISION
Wichita, Kansas