

130 South Market, Rm 2078
Wichita, Kansas 67202

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

WELL NUMBER 1
1250 Ft. from N Section Line

1250 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

SEC. 29 TWP. 34S RGE. 39 (E) or (W)

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

COUNTY MORTON

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 11/22/77

Character of Well GAS

Plugging Commenced 9/30/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/01/97

The plugging proposal was approved on 09/15/97 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 2920' Bottom 3081' T.D. 3110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2920'	3081'	8-5/8"	638'	4'
				4-1/2"	3110'	4'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU, PMP 3 SXS HULLS & 20 SXS CMT. DISPLACE W/9 PPG MUD TO 1300. PMP 110 SXS CMT. APPROX CMT PLG DEPTHS 2920-2720 & 1300-0. PMP 20 SXS CMT IN 4-1/2" & 8-5/8" ANNULUS. CUT OFF & CAP 8-5/8" & 4-1/2" CSG 4' BELOW GL. INSCRIBE CAP. RESTORE LOCATION. PLUGGING WITNESSED BY KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

1997 DEC 24 1:02

RECEIVED ANADARKO PETROLEUM CORPORATION
SUBSCRIBED AND SWORN TO before me this 22 day of December, 1997.

Shirley J. Childers
Notary Public

My Commission Expires: 11/14/98

