

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-2223000000

LEASE NAME PFEIFER "C"

WELL NUMBER 2

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 34 RGE. 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 10-15-97

Plugging Commenced 10-15-97

Plugging Completed 10-16-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-15-97 (date)

by DODGE CITY DISTRICT OFFICE (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6500

Show depth and thickness of all water, oil and gas formations.

11-21-97
10 20 30 40 50 60 70 80 90 100
10 20 30 40 50 60 70 80 90 100

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 13-3/8" | 530 | NONE |
| | | | | 8-5/8" | 1750 | NONE |
| | | | | | | |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. TIH W/4 1/2" DP TO 3300' & SET 100 SKS 60/40 POZMIX, 6%GEL @ 3300', TOH TO 1780' & SET 50 SKS, TOH TO 580' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 13-3/8" & 8-5/8" CSG 3' BELOW GI AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP. KCC REP: STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DUKE DRILLING License No. 5929

Address 310 W. CENTRAL, STE. 202, WICHITA, KANSAS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 11-18-97

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1997.

Mona L. Hinz
Notary Public

My Commission Expires:

