

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-21,011-0000 (of this well) 3/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Shepler & Thomas, Inc. OPERATORS LICENSE NO. 3711

ADDRESS P.O. Box 1162, Liberal, KS 67905-1162 PHONE # (316) 624-0750

LEASE (FARM) Dreitz WELL NO. 1-11 WELL LOCATION 1/4 NE-SW COUNTY Seward

SEC. 11 TWP. 32S RGE. 31 (O) or (W) TOTAL DEPTH 6000 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1629 CEMENTED WITH 605 SACKS

CASING SIZE 4 1/2 SET AT 5999 CEMENTED WITH 370 SACKS

PERFORATED AT 5909-11; 5715-20; 4888-92; 4876-81; 4931-34

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mud from 5999-5850; CIBP @ 5850 with 2 sx cement on top; water from 5850-5000'; CIBP @ 5000 with 2 sx cement on top; water from 5000 to CIBP @ 4840 with 2 sx cement on top. RU plugging contractor, cut off @ free point and spot 50 sx cement. Mud from cutoff plug to 1680; 100 sx cement from 1680-1580; mud to 750; 30 sx @ 750-650; mud to 40', 10 sx cement from 40'-3', 15 sx in RH, 10 sx in MH, int off and cap 3' below G.L. (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 A.M. on 5/2/88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION. RECEIVED
STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
R. F. Burke MAY 04 1988
PHONE # (316) 624-0750

ADDRESS P.O. Box 1162, Liberal, KS 67905-1162 CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Sargents Casing Pullers LICENSE NO. 6547

ADDRESS 620 South Lincoln, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: RFB
(Operator or Agent)

DATE: 5/2/88

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

AUG 05 '88

EXPIRES

May 5, 1988

WELL PLUGGING NOTICE

Dreitz #1-11
SW NE SW
Sec. 11-32S-31W
Seward County

Shepler & Thomas, Inc.
P. O. Box 1162
Liberal, KS 67905-1162


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760