

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

RECEIVED
KANSAS STATE CORP. COMM.
NOV DEC 22 5 3:12
KCC LICENSE # 6568 6/98

API # 15-175-20100-0003 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kaiser-Francis Oil Company (owner/company name) KCC LICENSE # 6568 (operator's)

ADDRESS P. O. Box 21468 CITY Tulsa

STATE OK ZIP CODE 74121-1468 CONTACT PHONE # (918) 491-4314

LEASE Manka WELL# 1 SEC. 25 T. 32S R. 31 (~~East~~/West)

-N/2 - NW - NW SPOT LOCATION/QQQQ COUNTY Seward

4770 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

4620 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1580 CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4473 CEMENTED WITH 150 SACKS

Liner 4 1/2 Set at 4080'-6130'

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3070-74; 3093-96; 3132-35; 3174-77

ELEVATION 2776 T.D. 6130 PBDT 4610 ANHYDRITE DEPTH n/a
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 3020' w/10' cmt on top. Pull stretch in 5 1/2" & pull all free pipe. Spot 75 sxs cmt in & out of 8 5/8" csg @ 1580'. Cut off pipe 3' below GL and cap.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Phill Goodwin, Supt. PHONE# (806) 435-6670

ADDRESS P. O. Box 746 City/State Perryton, TX

PLUGGING CONTRACTOR Sargent's Casing Pulling Service KCC LICENSE # 6547 6/98

ADDRESS P. O. Box 506, Liberal, KS 67901 (company name) PHONE # (316) 624-7455 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/19/97 AUTHORIZED OPERATOR/AGENT: C. Jan Valkenburg

(signature)
Charlotte Van Valkenburg

Company Leben Drilling, Inc.

Sec. 25 T. 32S R. 31W

Contractor Leben Drilling, Inc.

Loc. 150' NE of C NW NW

Farm Manka #1


County Seward

Total Depth 6130'

Casing 8 5/8" New 24# Casing set @ 1580'
w/600 sxs. 50/50 Poz. 6% Gel, 2% G.C.
Production 225 sxs. Common 2% G.C.

Commenced 3-20-70

Completed 4-15-70



Figures Indicate Bottom of Formations

133	Surface
935	Sand & Red Bed
1575	Red Bed
1590	Anhydrite
2103	Gyp & Shells
2463	Shale & Shells
3176	Lime & Shale
3281	Lime
3504	Lime & Shale
3701	Lime
4172	Lime & Shale
4179	Lime
4445	Lime & Shale
6130	Lime
<u>6130</u>	<u>RTD</u>

State of Kansas

County of Barton

SS

I, James R. Rodgers of Leben Drilling, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the Manka #1 Well.



1997 DEC 22 2:12

RECEIVED KANSAS CORP COMM

James R. Rodgers

sworn to before me this 21st day of April, 1970

My Commission Expires: November

Helen L. Lindenmuth



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

December 23, 1997

Kaiser-Francis Oil Company
P O Box 21468
Tulsa OK 74121-1468

Manka #1
API 15-175-20,100
4770 FSL 4620 FEL
Sec. 25-32S-31W
Seward County

Dear Sargent's Casing Pulling Service,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760