

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20100-0003 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Leben Oil Corporation OPERATOR'S LICENSE NO. 6566 6/91

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468 PHONE # (918) 494-0000

LEASE (FARM) Manka WELL NO. 1 WELL LOCATION N/2 NW NW COUNTY Seward

SEC. 25 TWP. 32S RGE. 31 (E) or (W) TOTAL DEPTH 6130 PLUG BACK TD 4610

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8 SET AT 1580 CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2 SET AT 4473 CEMENTED WITH 150 SACKS
Liner 4 1/2 Set At 4080-6130 Cemented With 425 Sacks

PERFORATED AT 3070-74; 3093-96; 3132-35; 3174-77

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 3020' w/10' cmt on top. Pull stretch in 5 1/2"

& pull all free pipe. Spot 75 sxs cmt in & out of 8 5/8" @ 1580'. Cut off pipe 3'

below G.L. and cap.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7/30/90 8 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Phill Goodwin, Supt. PHONE # (806) 435-6670 JUN 28 1990

ADDRESS P. O. Box 746, Perryton, TX 79070

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 6/91

ADDRESS Box 506, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.


SIGNED: C. Jan Falkenberg
(Operator or Agent)

DATE: 6/26/90

①

Company Leben Drilling, Inc.
 Contractor Leben Drilling, Inc.
 Farm Manka #1
 Total Depth 6130'
 Commenced 3-20-70
 Completed 4-15-70

Sec. 25 T. 32S R. 31W
 Loc. 150' NE of C NW NW
 County Seward
 Casing 8 5/8" New 24# Casing set @ 1580'
 w/600 sxs. 50/50 Poz. 6% Gel, 2% G.C.
 Production & 225 sxs. Common 2% G.C.




Figures Indicate Bottom of Formations

133	Surface
935	Sand & Red Bed
1575	Red Bed
1590	Anhydrite
2103	Gyp & Shells
2463	Shale & Shells
3176	Lime & Shale
3281	Lime
3504	Lime & Shale
3701	Lime
4172	Lime & Shale
4179	Lime
4445	Lime & Shale
6130	Lime
<u>6130</u>	<u>RTD</u>

JUN 23 1970

State of Kansas
 County of Barton
 SS

I, James R. Rodgers of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Manka #1 Well.



James R. Rodgers

sworn to before me this 21st day of April, 1970

My Commission Expires: November

Helen L. Lindenmuth



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
OCT 10 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

July 10, 1990

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Leben Oil Corporation
P.O. Box 21468
Tulsa, OK 74121-1468

Manka 1
N/2 NW NW
Sec. 25-32-31w
Seward County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760