

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 063-21500 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Jerry Green / Castle Resources, Inc. KCC LICENSE # 9860
(owner/company name) (operator's)

ADDRESS 1200 East 27th, Suite C CITY Hays

STATE Kansas ZIP CODE 67601 CONTACT PHONE # (913) 825-5155

LEASE Jim Coberly WELL# 1 SEC. 7 T. 15s R. 27W (East/West)

S/2 - NW - SE SPOT LOCATION/0000 COUNTY Gove

1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 202.55 CEMENTED WITH 140 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2505/2513 T.D. 4330 FBTD _____ ANHYDRITE DEPTH (1962-1997)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 1990' w/25sks)(2nd Plug @ 910' w/100sks)

(3rd Plug @ 255' w/40sks)(4th Plug @ 40' w/10sks)(10sks In Mouse Hole)(15sks In Rat)

200sks 60/40Poz 6%Gel w/1/4#FS/sk By Allied Cementing Completed @ 4:15PM 4/7/97

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas H. Alm PHONE# (913) 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Discovery Drilling, Inc. KCC LICENSE # 31548

ADDRESS P.O. Box 763 Hays, Kansas 67601 PHONE # (913) 623-2920
(contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) 4/7/97 4:15PM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/24/97 AUTHORIZED OPERATOR/AGENT: _____

(signature)

RECEIVED
APR 0 4 1997
KANSAS CORPORATION COMMISSION