

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Littrell of Mobil Oil has this date requested permission to plug the following described well:

Mr. Littrell guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corp.

Complete Address: Box 400, Hugoton, Kansas

Lease Name: Ratcliffe Fee Well No. 1

Location: NE Sec. 7 Twp. 34 Rge. 38 ~~(E)~~ (W)

County: Stevens Total Depth 2832' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Litrell was instructed to plug the well as follows:

12 1/2" to 573' circulated w/ cement. 8 5/8" to 2556' circulated w/ cement.


7" liner 2540' to 2832' Plug bottom w/ 20 sacks cement

Top of cement 2150' Mud 2150' to 623'

Spot 35 sacks cement 623' to 500' Mud 500' to 60'

Plug, Hulls & 15 sacks cement 60' to 0'.

Very truly yours,


Conservation Division Agent