

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gatlin of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Funk "A" Well No. 1

Location: C SW SW 1/4 Sec. 4 Twp. 34 Rge. 38 (W)

County Stevens Total Depth 6800' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1747' circulated w/ cement. T.D. 6800'

Mud 6800' to 3000' Spotted 25 sacks cement 3000' to 2920'

Mud 2920' to 700' Spotted 35 sacks cement 700' to 590'

Mud 590' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent