

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: E. G. Mingenback O/A Well No. 1

Location: App. Center Sec. 31 Twp. 34 Rge. 39 (W)

County Morton Total Depth 2815' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

8 5/8" to 515' ciru. w/ cement. 5 1/2" to 2814' ciru. w/ cement.

3 1/2" to 1510' w/ Packer Top perforations 2644'

Plug bottom w/ 30 sacks cement Top of cement 1360'

Mud 1360' to 500' Spotted 25 sacks cement 500' to 325'

Mud 325' to 75' Plug, Hulls& 10 sacks cement 75' to 0'

Very truly yours,

Edgar J. Eves  
Conservation Division Agent