

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Strauch of Mobil Oil Corp. has this
date requested permission to plug the following described well:Mr. Strauch guarantees payment of the plugging fee.Operator's full Name: Mobil Oil Corp. Attn: A.J. MoredieComplete Address: P O Box 5444 Denver, Colo. 80217Lease Name: Elijah D. Thompson Unit Well No. 1Location: C NE/4 Sec. 19 Twp. 34 Rge. 39 (E)(W) XCounty: Morton Total Depth 1454' Oil Well Gas Well Input Well SWD Well D & A Lost Hole XMr. Strauch was instructed to plug the well as follows:Spot 50 sx cement at 879'.Fill hole with mud and spot 50 sx cement at 630'.Fill hole with mud to 40' and 1/2 sx hulls, plug, and10 sx cement. 5 sx cement in rat hole.772' of 3 5/8" surface casing cement circ.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1979
CONSERVATION DIVISION
Wichita, Kansas