

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Marion Dale of Walter Kuhn Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Marion Dale guarantees payment of the plugging fee.

Operator's full Name: Walter Kuhn Drilling Co.

Complete Address: 726 Union Center. Wichita, Kansas

Lease Name: Armstrong Well No. # 1

Location: SE 1/4 Sec. 16 Twp. 34 Rge. 39 (E) (W)

County Morton Total Depth 2781' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Marion Dale was instructed to plug the well as follows:

10 3/4" 587' 7" 2590'

Plug bottom w/cement 2781' to 1903'

Mud 1903' to 500' 50 sax.cement 500' to 415'

Mud 415' to 50' Rock Bridge 50' to 40'

20. sax.cement 40' to 0

Very truly yours,

[Signature]
 Conservation Division Agent