

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Stevens Co. Oil & Gas has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.Operator's full Name: Stevens Co. Oil & Gas CompanyComplete Address: 301 American Savings Bldg., Wichita, KansasLease Name: Jenkins Well No. 1Location: C SW Sec. 10 Twp. 34 Rge. 39 (E) (W)County: Stevens Total Depth 2700' Oil WellGas Well X Input Well      SWD Well      D & A X Lost Hole     Mr. Hanna was instructed to plug the well as follows:

13 3/8" to 675' circulated w/ cement. 8 5/8" to 2580' cemented.

Open hole 2580' to T.D. Plug bottom w/ 85 sacks cement.

Top of cement 2395' Mud 2395' to 500'

Spot 65 sacks cement 500' to 400' Mud 400' to 25'

Plug, Halls &amp; 15 sacks cement 25' to 0'.

Very truly yours,

  
 Conservation Division Agent