

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. McCune of Cities Service Oil Co. has this
date requested permission to plug the following described well:

Mr. McCune guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1028, Guymon, Oklahoma

Lease Name: Cyr "B" Well No. 1

Location: C SE SW Sec. 32 Twp. 34 Rge. 417 (X) (W)

County Morton Total Depth 5116' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McCune was instructed to plug the well as follows:

- 8 5/8" to 1446' ciru. w/, cement. Spotted 25 sacks cement 5100' to 5025'
- Mud 5025' to 4840' Spotted 25 sacks cement 4840' to 4765'
- Mud 4765' to 3305' Spotted 25 sacks cement 3305' to 3230'
- Mud 3230' to 3100' Spotted 25 sacks cement 3100' to 3025'
- Mud 3025' to 700' Spotted 35 sacks cement 700' to 600'
- Mud 600' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Evers
Conservation Division Agent