

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Carson of Cities Service Oil has this

date requested permission to plug the following described well:

Mr. Carson guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1228, Guymon, Oklahoma

Lease Name: Ward "D" Well No. 1

Location: App. C Sec. 27 Twp. 34 Rge. 41 (E) (W)

County Morton Total Depth 2375' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Carson was instructed to plug the well as follows:

8 5/8" to 360' circulated w/ cement. 5 1/2" to 2374' circulated w/ cement.

Top perforations 2256' Plug bottom w/ 50 sacks cement

Top of cement 1850' Mud 1850' to 882'

Spot 25 sacks cement 882' to 667' Mud 667' to 90'

Plug, Hulls & 15 sacks cement 90' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent