

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 109-33

LOCATION CNE

SEC. 8 TWP. 32 RGE. 32W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Collingwood, B.

Operator Prince Brothers Drilling Co. Address BOX 992, Electra, Texas

Field Hugoton, County Seward

Total Depth 2685 Feet.

Plugging Contractor Arnett Well Plugging

Plugging Contractor's License No. _____

Address Holsington, Kansas

(Describe briefly the manner in which the well was plugged)

Pumped 150 sacks of cement through perforations	2650 to 2684
Top of plug 2656. Mud	540 to 2556
Rock bridge	530 to 540
Dumped 10 sacks of cement	495 to 530
Bailed hole dry, tested for water 2 hours. No water entry	
Dumped 10 sacks of cement	460 to 495
Mud	40 to 460
Rock bridge	35 to 40
Dumped 10 sacks of cement	2 to 35
Cut off 8 5/8 casing 4 feet below surface	

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 X 1955

CONSERVATION DIVISION
Wichita, Kansas

T. J. Phillinger
District Conservation Agent

Date July 16, 1955

PLUGGING
FILE SEC 8 T 32 R 32W
PAGE 109 LINE 33