

15-095-20871-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 095 20,871-0000 (of this well)

Operator's Full Name Con-Am Inc.

Complete Address One Main Place, Suite 600, Wichita, Ks. 67202

Lease Name Kostner Well No. 1

Location C SW NW Sec. 6 Twp 29S Rge. 5 (E) (W) X

County Kingman Total Depth 3960

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

~~Other well as hereinafter indicated~~ T D of this well is 3960' not 3956'.

Plugging Contractor Glenn's Casing Pulling Inc.

Address Box 413-Ellingwood, Ks. 67526 License No. 832

Operation Completed: Hour 1:30 Pm Day 11 Month 8 Year 1980

The above well was plugged as follows:

381' 8 5/8" casing w/350 sax cement. 4 1/2" casing set at 3956' w/75
sax cement. Preforated at 3891 to 95'-Allied mixed & pumped in 4 1/2"
casing 35 sax common cement to 3751'-Pull 3006' 4 1/2" casing-Allied
mixed & pumped in 8 5/8" casing 8 sax hulls-25 sax gel-125 sax 50/50
posmix cement w/4% gel & 3% cc to top of casing. Shut in w/500# press

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-14-80

IN. NO. 2852-W