

To: 1 100072
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-189-20,567-W ⁰⁰⁰¹

C W/2 SE, SEC. 23, T 32 S, R 38 W/E

1320 feet from S section line

1980 feet from E section line

Lease Name Nordling A Well # 1H.

County Stevens 96.16

Well Total Depth 2959 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1768

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation

Name: P.O. Box 351.

Address: Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bruce Well Service License Number 7407

Address P.O. Box 1597, Liberal, KS 67905-1597

Company to plug at: Hour: 11 a.m. Day: 23 Month: 10 Year: 96

Plugging proposal received from Myron Hesston

(company name) Bruce Well Service (phone) _____

Work: 5 1/2" at 2925' w/260 sx cement, PBTD 2924', Perfs at 2565-2796' (5 sets)

1st plug set CIBP at 2500',

Circulate hole with mud, 2nd plug run tubing to 1800' and spot 15 sx cement, pull out of hole,

3rd plug perforate at 650' and circulate cement inside and out.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 23 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT

1st plug set CIBP at 2550'. Ran tubing to 2550' and circulated hole with mud. 2nd plug pulled tubing to 1800' and spotted 15 sx cement, pulled tubing,

3rd plug perforated at 690' and circulated hole. Pumped 171 sx cement, circulated 10 sx to pit.

Displaced cement to 650'. Mixed 2 sx cement for temporary cap from 50-0'.

Left well shut in. Operator plans to reenter the hole at a later date.

Remarks: Used 60/40 Pozmix .6% gel by Halliburton. No casing recovery. (if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 10-31-96

Signed Gary Winters (TECHNICIAN)

INV. NO. 4886

10-23 JAN 06 1997

RECEIVED
OCT 30 1996
WICHITA STATE OFFICE

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20567-W

LEASE NAME NORDLING "A"

WELL NUMBER 1-H

1320 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 23 TWP. 32S RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 4/28/87

Plugging Commenced 10/23/96

Plugging Completed 10/23/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/18/96 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2565 Bottom 2796 T.D. 2925

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	OIL	2565	2796	8-5/8"	1768	3'
				5-1/2"	2925	3'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
P&A'D AS FOLLOWS: SET CIBP @ 2550, DMP 2SXS CMT ON CIBP. SPOT 15SXS CLASS "H" CMT PLG. FROM 1824-1710. RIN & PERF CMT SQZ HOLES @ 690'. CIRC CMT TO SURF W/170SXS CLASS "H". DISPLACE W/MUD TO 650. SPOT PLG FROM 40-0' W/5SXS CMT. CAP 3' BELOW GL RDMO WL & PU. KCC WITNESS: GARY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1997

My Commission Expires:



Notary Public