

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

15-189-19014-0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

PLEASE TYPE FORM and File ONE Copy)

API # (DRILLED IN 1930) (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 ^{8/98}
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE MORRIS WELL# 1-29 SEC. 29 T. 34S R. 38 (XXXX/West)

- - C - SE SPOT LOCATION/QQQQ COUNTY STEVENS

1320 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE 12-1/2" SET AT 628' CEMENTED WITH NA SACKS

SURFACE CASING SIZE 8-5/8" SET AT EST 2595' CEMENTED WITH NA SACKS

PRODUCTION CASING SIZE 7" SET AT 2935' CEMENTED WITH 50 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 2696-2926 O.A.

ELEVATION 3268' / -- T.D. 2935' PBSD 2936' ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH W/1-1/4" WS TO 2935'. SPOT 80 SXS CMT @ 2935-2600'. PULL ON 7" CSG & LOCATE FREE POINT. SHOOT OFF 7" CSG. SPOT 20 SXS CMT AS A 50' CMT PLUG @ CUT OFF POINT. SPOT 20 SXS CMT @ 54-4'. CUT OFF SURFACE CSG 4' BELOW GL & CAP. INSCRIBE CAP. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151 ^{1/98}
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/13/98 AUTHORIZED OPERATOR/AGENT: Shawn D. Young RECEIVED

SHAWN D. YOUNG (Signature)
DIVISION PRODUCTION ENGINEER

JAN 16 1998
1-16-98
CONSERVATION DIVISION
Wichita, Kansas

ANADARKO PETROLEUM CORPORATION

PHONE 316 - 624 - 6253 1701 NORTH KANSAS AVE. P.O. BOX 351 LIBERAL, KANSAS 67905 - 0351



January 12, 1998

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202

Attn.: Ms. Janet Pierce

Re: Well Plugging Application Form (Form CP-1)

Morris 1-29
Sec. 29-34S-38W
Stevens County, Kansas

Dear Janet:

Enclosed in duplicate is a well plugging application (Form CP-1) for the referenced well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

Shawn D. Young
Division Production Engineer
AMC/sjc

Enclosures

cc: Well File
TRC - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.doc

STATE

COMMISSION

JAN 16 1998

WICHITA, KANSAS



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 21, 1998

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Morris #1-29
API 15-N/A
1320 FSL 1320 FEL
Sec. 29-34S-38W
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, reading "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760