

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

15-189-00671-0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # NA (SPUD 12/14/46) (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549 ^{8/97}
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE (SMITH) Young WELL# 1 (1-14) SEC. 14 T. 34S R. 39 (xxxx/West)

- - - C - SW SPOT LOCATION/QQQQ COUNTY STEVENS

1320 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM (W) E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 10-3/4" SET AT 561' CEMENTED WITH 100 SACKS

PRODUCTION CASING SIZE 7" SET AT 2619' CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 5-1/2" SLOTTED LINER @ 2593'-2777'

ELEVATION 3303' / -- T.D. 2777' PBDT 2765' ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING NOTIFY KCC DISTRICT OFFICE 72 HRS PRIOR TO PLUGGING. MIRU PU. SET CIBP @ 2550'. SPOT 2 SXS CLASS H CMT ON TOP. CIRC HOLE W/ 9PPG MUD. SPOT CMT PLUG FROM 610'-510'. PULL UP HOLE & SPOT CMT PLUG FROM 53'-3'. CUT OFF & CAP 10-3/4" & 7" CSG 3' BELOW GL. PERMANENTLY INSCRIBE CAP WITH WELL NAME & NO, LEGAL DESCRIPTION, & PLUGGING DATE. RDMO PU. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NOT AVAIL.

If not explain why? NO WELL LOGS AVAILABLE

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. DAVE GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES KCC LICENSE # 3887
(company name) (contractor's)

ADDRESS P.O. BOX 1598, LIBERAL, KS 67905-1598 PHONE # (316) 624-3879

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/5/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (signature)
DIVISION PRODUCTION ENGINEER

RECEIVED
KANSAS CORPORATION COMMISSION
APR 1 1997



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

March 7, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Smith #1-14
API 15-N/A
1320 FSL 1320 FWL
Sec. 14-34S-39W
Stevens County

Dear Mr. Dave Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760