

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Finney State Office Building  
130 South Market  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

RECEIVED

FEB 11 2002

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

KCC WICHITA

API # 15-129-216590000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS 701 S. TAYLOR, SUITE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE # (806) 457-4600

LEASE HJV CORNELL UNIVERSITY "C" WELL# 1 SEC. 7 T. 34S R. 39 (XXXX/West)

- NW - NW - SW SPOT LOCATION/QQQQ COUNTY MORTON

2310 FEET (in exact footage) FROM X/S (circle one) LINE OF SECTION (NOT LeaseLine)

330 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT LeaseLine)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#                     

CONDUCTOR CASING SIZE                      SET AT                      CEMENTED WITH                      SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1730' CEMENTED WITH 520 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 5012' CEMENTED WITH 165 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4802-18, CIBP @4760'

ELEVATION 3325 -                      T.D. 6450 PBSD 4760 ANHYDRITE DEPTH                       
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE   
PROPOSED METHOD OF PLUGGING MIRU PU. TIH W/2-3/8" TBG TO 4760'. LOAD HOLE W/MUD. SPOT 4 SXS CLASS H CMT @4760'. TOH W/TBG. LOCATE 5-1/2" CSG FREE POINT. BACK OFF 5-1/2" CSG AT FREE POINT. TOH W/5-1/2" CSG TO 1780' & SPOT 40 SXS CLASS H CMT FROM 1780' TO 1680'. DISPLACE W/9 PPG MUD. TOH W/5-1/2" CSG TO 630' & SPOT 40 SXS CLASS H CMT FROM 630' TO 530'. DISPLACE W/9 PPG MUD. TOH W/5-1/2" CSG TO 40' & SPOT 10 SXS CLASS H CMT FROM 0' TO 40'. DISPLACE W/9 PPG MUD. TOH W/CSG. WOC. CUT OFF & CAP 8-5/8" CSG 3' BELOW GL. INSCRIBE WELL NAME & NUMBER, LEGAL DESCRIPTION AND DATE PLUGGED ON STEEL CAP. RDMO PU & RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JOHN VIGIL PHONE# (806) 457-4600

ADDRESS 701 S. TAYLOR, SUITE 400 City/State AMARILLO, TEXAS 79101

PLUGGING CONTRACTOR: SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT. 1, BOX 49 BA, TYRONE, OK 73941-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 02/07/02 AUTHORIZED OPERATOR/AGENT: John M. Vigil  
JOHN M. VIGIL (signature)  
DIVISION DRILLING COORDINATOR

8/02

1/03



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
17001 Northchase Drive  
Houston, TX 77060

February 26, 2002

Re: HJV CORNELL UNIV C #1  
API 15-129-21659-00-00  
NWNWSW 7-34S-39W, 2310 FSL 330 FWL  
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely,

A handwritten signature in black ink that reads "David P. Williams".

David P. Williams  
Production Supervisor