

To: 1 052119 4-7
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-22,152-0000
NW SE SE, SEC. 30, T 34 S, R 38 W/E
1250 feet from S section line
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9736
Operator: Dorchester Hugoton, Ltd.
Name & Address: 9696 Skillman St., Ste. 320
Dallas, TX 75243-8200

Lease Name Huxman Well # I-3
County Stevens 47,48
Well Total Depth 1461 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 622

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Norseman Drilling, Inc. License Number 3779
Address 200 E. 1st, Ste. 307, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 7 Month: 4 Year: 19 97

Plugging proposal received from John Donnelly
(company name) Dorchester Hugoton, Ltd. (phone) 214-340-3443

Work: to fill hole with heavy mud and spot cement through drill pipe
Lost circulation at 1414'

1st plug at 1200' with 50 sx cement,

2nd plug at 650' with 50 sx cement, 3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement, 5th plug to circulate mousehole with 10 sx
cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 a.m. Day: 7 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement (thixotropic),

2nd plug at 650' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS CORP COM
1997 APR - 8 A 10:40

Remarks: Used 60/40 Pozmix 6% gel and thixotropic by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

DATE APR 09 1997

INV. NO. 47897

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
HUGOTON INFILL

CARD MUST BE SIGNED
SGA-NO

EFFECTIVE DATE 2-19-97

Starting Date 03 10 97
month day year

API Number 15 - 189-221520000

OPERATOR: License # 09736
Name Dorchester Hugoton, Ltd.
Address 9696 Skillman St., Suite 320
City/State/Zip Dallas, TX 75243-8200
Contact Person Johnny L. Booth
Phone (214) 340-3443

CONTRACTOR: License # 3779
Name Norseman Drilling, Inc.
City/State Wichita, KS

Well Drilled as: New Recompletion OWWO
Projected Total Depth 2,930 feet
Formation Chase

If OWWO or Recompletion: old well info as follows:
Operator _____
Well Name _____
Comp. Date _____ Old Total Depth _____

IS SECTION REGULAR IRREGULAR
NW/4 SE/4 SE/4 Sec. 30 Twp. 34 S, Rg. 38 W
1,250 Ft. from South Line of Section
1,250 Ft. from East Line of Section

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit 640
Nearest producing well from _____
same common source of supply 2,570 feet
Nearest lease or unit boundary line 1,250 feet
County Stevens
Lease Name Huxman Well # I-3
Ground surface elevation 3,286.4 feet MSL
Depth to bottom of fresh water 510
Depth to bottom of usable water 540-580
Surface pipe by Alternate: 1 X / 2
Surface pipe planned to be set 600'
Water Source for Drilled Operations: _____

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 02/12/97 Signature of Operator or Agent Johnny L. Booth Title Mgr. Mktg./Royalties _____

For KCC Use:
Conductor Pipe Required NONE feet; Minimum Surface Pipe Required 600' feet per Alt.
This Authorization Expires 8-14-97 Approved By JK 2-14-97

9/95

RECEIVED
KANSAS CORP COME 4-7-97
1997 APR - 8 A 10:41

Pusher Tahn Kancellly

SPUD DATE 3-31-97 INIT. A.L.

LENGTH SURFACE PLANNED 9 5/8 622

RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
after salt sect. _____ bbls. when done _____ bbls.

RATHOLED AHEAD? Y N SIZE HOLE _____

SURFACE PIPE 8 5/8 @ 622 CONDUCTOR _____

ANHYDRITE T- _____ B- _____ ELEVATION _____

CD 1461 FORMATION Lost Circ @ 1414 can get back

RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
SX Y N

Arbuckle Plug @ _____ Ft. W/ _____ SX

Hng./Council @ _____ Ft. W/ _____ SX

Anhydrite Base @ _____ Ft. W/ _____ SX

1/2 Base Anhy. @ 1200 Ft. W/ 90 SX

1/2, 1/2 Plug @ _____ Ft. W/ _____ SX

Bottom Surface @ 650 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
HAULING _____

TECHNICIAN A.L. DATE 4-5-97

TYPE OF CEMENT _____

STARTING TIME 1:00 (AM/PM) DATE 4-7-97

COMPLETION TIME 6:45 (AM/PM) DATE 4-7-97

CEMENT COMPANY Halliburton

11.71 skid hole 50' west

have 4 workers 4 days
this is tropic
6040 poz
6 5/8
17-2