

To: 1 100203
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

2-27

15-189-19014-0000
API NUMBER 15-Drilled 1930 15-189-19014-00-00

C SE, SEC. 29, T 34 S, R 38 ~~XX~~

1320 feet from S section line

1320 feet from E section line

Lease Name Morris Well # 1-29

County Stevens 95.39

Well Total Depth 2935 feet

Conductor Pipe: Size 12 1/2 feet 628

Surface Casing: Size 8 5/8 feet 2595

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt.1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 25 Month: 2 Year: 19 98

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 7" at 2935' w/50 sx cement, Perfs at 2696-2926'

1st plug set CIBP at 2650' with 5 sx cement on top,

2nd plug run tubing to 650' and pump 100 sx cement,

3rd plug pull tubing to 90' and top off with 50 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 27 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2646' with 5 sx cement on top,

shot at 2000', shot at 1810', shot at 1514', shot at 940'. Pulled 7" out of hole, pulled 8 5/8" out of hole.

2nd plug ran tubing to 650' and spotted 100 sx cement at 650',

3rd plug pulled tubing to 90' and topped off with 50 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 940' of 7" & 940' of 8 5/8" casing (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-10-98

INV. NO. 50183

2-27

Signed Gary Winters (TECHNICIAN)

RECEIVED
KANSAS
STATE
CORPORATION
COMMISSION
3-9-98
11:42