

To: 100190
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

1-21

API NUMBER 15-189-21,247-0000

NW SE SE, SEC. 24, T. 34 S, R. 38 WEX

1250 feet from S section line

1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Elliot B Well # 1H

Operator: Anadarko Petroleum Corporation

County Stevens 97.73

Name: P.O. Box 351

Well Total Depth 3007 feet

Address: Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 652

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 20 Month: 1 Year: 19 98

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 5 1/2" at 3003' w/255 sx cement, PBD 2850', Perfs at 2657-2968', TOC 700' Cmt. Bond Log

1st plug pump 400 lbs. hulls with 25 sx cement from 2657-2457',

2nd plug pump 50 sx cement at 700', displace with mud,

3rd plug pump 10 sx cement from 40-0'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 21 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs.hulls with 25 sx cement from 2657-2457',

2nd plug pumped 50 sx cement at 700', displaced with mud,

3rd plug pumped 10 sx cement at 40-0'.

RECORDED
STATE CORPORATION COMMISSION
1-27-1998
JAN 27 1998

Remarks: Used common cement by Sargent & Horton. Recovered 703' of 5 1/2" casing.

INVOICED
If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE: JAN 28 1998

Signed Gary Winters (TECHNICIAN)

INV. NO. 49988

1-21