

070034

10-14

R

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. NW
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-22,236 - 0000
NE SW, SEC. 14, T 34 S, R 38 W/E
2150 feet from S section line
1480 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5363
Operator: BEREXCO, Inc.
Name & Address 100 N. Broadway, Ste. 970
Wichita, KS 67202

Lease Name Della Well # 1-14
County Stevens 210.93
Well Total Depth 6490 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1764

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Sweetman Drilling License Number 5658
Address 3017 N. Cypress Dr., Wichita, KS 67226-4003

Company to plug at: Hour: 4 p.m. Day: 14 Month: 10 Year: 19 97

Plugging proposal received from Eugene Saloga

(company name) Sweetman Drilling (phone) 316-634-6151

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1757'

- 1st plug at 3200' with 100 sx cement, 2nd plug at 1790' with 50 sx cement,
- 3rd plug at 680' with 50 sx cement, 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 p.m. Day: 14 Month: 10 Year: 19 97

- ACTUAL PLUGGING REPORT
- 1st plug at 3200' with 100 sx cement,
 - 2nd plug at 1790' with 50 sx cement,
 - 3rd plug at 680' with 50 sx cement,
 - 4th plug at 40' with 10 sx cement,
 - 5th plug to circulate rathole with 15 sx cement,
 - 6th plug to circulate mousehole with 10 sx cement.

10-14-1997
OCT 17 11 47 AM '97
V.A. State Office Bldg.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 22 1997
INV. NO. 49039
10-14

Signed [Signature] (TECHNICIAN)

