

To: 1 031405  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 189-22,082-0000  
NE SW, SEC. 6, T 34 S, R 38 W X  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5003  
Operator: McCoy Petroleum Corporation  
Name & Address: 3017 N. Cypress  
Wichita, KS 67226

Lease Name Gloria Well # 1-6  
County Stevens  
Well Total Depth 6404 208.13 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1794

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sweetman Drilling Inc. License Number 5658  
Address 3017 N. Cypress, Wichita, KS 67226

Company to plug at: Hour: \_\_\_\_\_ Day: 30 Month: 7 Year: 19 96

Plugging proposal received from Eugene Saloga  
(company name) Sweetman Drilling Inc. (phone) 316-636-2737

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1790'  
1st plug at 3200' with 100 sx cement, 2nd plug at 1810' with 50 sx cement,  
3rd plug at 600' with 25 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 a.m. Day: 31 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,  
2nd plug at 1810' with 50 sx cement,  
3rd plug at 600' with 25 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-2-1996  
AUG 02 1996

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (check) did not observe this plugging.

DATE AUG 07 1996

Signed Steve Durrant (TECHNICIAN)

INV. NO. 46200  
7-31

FOR KCC USE:

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 6-23-96  
DISTRICT # 1  
SSA? Yes No

State of Kansas 15-189-22,082-0000

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 6 27 96  
month day year

Spot NE-SW- Sec 6 Twp 34 S, Rg 38 East

OPERATOR: License # 5003  
Name: McCoy Petroleum Corporation  
Address: 3017 N. Cypress  
City/State/Zip: Wichita, Kansas 67226  
Contact Person: Tim Pierce  
Phone: (316) 636-2737

1980 feet from South / North line of Section  
3300 feet from East / West line of Section  
IS SECTION X REGULAR IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Stevens  
Lease Name: Gloria Well #: 16  
Field Name: Gentzler SW Extension

CONTRACTOR: License #: 5658  
Name: Sweetman Drilling Inc.

\*Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Lower Morrow  
Nearest Lease or unit boundary: 660'  
Ground Surface Elevation: 3235' EGL  
Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 545'  
Depth to bottom of usable water: 600'  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 1750 +/-  
Length of Conductor pipe required: 40  
Projected Total Depth: 6400'  
Formation at Total Depth: Chester  
Water Source for Drilling Operations:  
X well farm pond other

Well Drilled For: Well Class: Type Equipment:  
Oil Erh Rec Infield X Mud Rotary  
X Gas Storage X Pool Ext. Air Rotary  
CWO Disposal Wildcat Cable  
Seismic; # of Holes Other  
If CWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:

Will Cores Be Taken? yes X no  
If yes, proposed zone: 620' ALT. 1 Req.

\*PRORATED AND SPACED RECEIVED  
IN CHASE AND KANSAS CORPORATION COMMISSION  
COUNCIL GROVE

Exp. 12/18/96

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

JUN 18 1996 6:00 PM

Pusher Eugene Sweetman  
SPUD DATE 7-19-96 INIT. SP.

LENGTH SURFACE PLANNED  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 5/8 @ 1794 CONDUCTOR  
ANHYDRITE T- 1790 B- ELEVATION  
TD 6404 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N

Arbuckle Plug @ Ft. W/ SX  
1 Plug./Council @ 3200 Ft. W/ 100 SX  
2 Anhydrite Base @ 1810 Ft. W/ 50 SX  
3 1/2 Base Anhyd. @ Ft. W/ SX  
3 1/2, 1/2 Plug @ 600 Ft. W/ 25 SX  
Bottom Surface @ Ft. W/ SX  
4 40' Plug @ 40-0 Ft. W/ 10 SX

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 02 1996  
OBSERVATION DIVISION  
WICHITA, KS  
TECHNICIAN SD DATE 7/30/96  
TYPE OF CEMENT 60/10 60%  
STARTING TIME (AM/PM) DATE  
COMPLETION TIME 12:30 (AM/PM) DATE 7-31-96  
CEMENT COMPANY Hall

RAT HOLE CIRC/W 15 SX ✓  
MOUSE HOLE W/10 SX  
WATER WELL 34 SX (Irr. Well) Bond  
Hauling