

4-11

To: 1 040263  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,319 - 2000  
C SE, SEC. 5, T 34 S, R 38 W/EX

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: P.O. Box 5444  
Denver, CO 80217

1320 feet from S section line  
1120 feet from E section line  
Lease Name Forward #1 Unit Well # 4  
County Stevens 216.74  
Well Total Depth 6675 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1768

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Unit Drilling & Exploration Co. License Number 9137  
Address P.O. Box 702500, Tulsa, OK 74136

Company to plug at: Hour: 8:45 a.m. Day: 11 Month: 4 Year: 19 89

Plugging proposal received from Danny White  
(company name) Mobil Oil Corporation (phone) 303-298-2069

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3223' GL  
Anhydrite 1740'  
1st plug at 5815' with 50 sx cement, 2nd plug at 2880' with 100 sx cement,  
3rd plug at 1780' with 50 sx cement, 4th plug at 870' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 p.m. Day: 11 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 5815' with 50 sx cement,  
2nd plug at 2880' with 100 sx cement,  
3rd plug at 1780' with 50 sx cement,  
4th plug at 870' with 50 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell Schlumberger.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
4-13-1989  
APR 13 1989

CONSERVATION DIVISION  
Wichita, Kansas

NOTICE: Observe this plugging.

DATE 4-24-89

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 24451

4-11 JUN 12 1989

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date MARCH 15 1989  
month day year

Approx: C-SE. Sec 5. Twp 34. S, Rg 38. East

OPERATOR: License # 5208  
Name: MOBIL OIL CORPORATION  
Address: P. O. BOX 5444  
City/State/Zip: DENVER, COL 80217  
Contact Person: B. R. Maynard  
Phone: (303) 298-2069

1320 feet from South line of Section  
1120 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: CONTRACTOR NOT SELECTED  
Name: WILL ADVISE ON ACO-1

unit # 19

County: STEVENS  
Lease Name: FORWARD #1 UNIT Well #: 4  
Field Name: OLSON  
Is this a Prorated Field? yes XX no  
Target Formation(s): MORROW  
Nearest lease or unit boundary: 1120'  
Ground Surface Elevation: 3222.6 feet MSL  
Domestic well within 330 feet: yes XX no  
Municipal well within one mile: yes XX no  
Depth to bottom of fresh water: .575'  
Depth to bottom of usable water: .600'  
Surface Pipe by Alternate: X. 1 . XX. 2  
Length of Surface Pipe Planned to be set: 625'  
Length of Conductor pipe required: None  
Projected Total Depth: 6700'  
Formation at Total Depth: 6200'  
Water Source for Drilling Operations:  
... well ... farm pond ... other

Well Drilled For: Well Class: Type Equipment:  
... Oil ... Inj X. Infield X. Mud Rotary  
X. Gas ... Storage ... Pool Ext. ... Air Rotary  
... ONWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If ONWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X... no  
If yes, total depth location:

DNR Permit #:  
Will Cores Be Taken: ... yes X... no  
If yes, proposed zone: WA


The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 52-101 et. seq.

AFFIDAVIT

PUSHER Danny Whitely recieved  
@ 6655  
TD WILLID@6675' FORMATION St. Louis.  
SURFACE PIPE 8 3/4" @ 1768'  
ANHYDRITE 1740' base ELEVATION 3223.66,  
STARTING TIME & DATE 8:45 AM 4-11-89  
COMPLETION TIME & DATE 3:00 PM 4-11-89  
50 SX plug in narrow top @ 5815'  
2nd PLUG @ 2880 FT. W/ 100 SX  
3rd PLUG @ 1780 FT. W/ 50 SX  
4th PLUG @ 870 FT. W/ 50 SX  
5th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ 10 SX  
WATER WELL PLUGGED W/ Land owned w/ 10 SX  
CEMENT COMPANY Dowell Schlumberger  
TECHNICIAN S.P. D.G.  
6046202 w/ 670.

6201 Het. 1 Reg. K.S.A. 52-101

RECEIVED  
4 STATE CORPORATION COMMISSION  
Set 1800 APR 13 1989  
M. Keller  
CONSERVATION DIVISION  
Wichita, Kansas



Spud date: MAR 2 1989 Agent: \_\_\_\_\_

- REMEMBER TO:
- File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.

38W