

TO: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202**

API Well Number: 15-189-21219-00-00
Spot: SESWNWSW Sec/Twnshp/Rge: 3-34S-38W
1370 feet from S Section Line, 4631 feet from E Section Line
Lease/Unit Name: BROOKS UNIT #1 Well Number: 4
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size _____ feet: 8 221.00
Surface Casing: Size 8.625 feet: 1771 WITH 775 SX CMT
Production: Size 5.5 feet: 6800 WITH 400 SX CMT
Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/20/2001 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 50 SX CMT AT 1800'. 40SX CMT AT 550'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2001 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 6644'. DV TOOL @ 3009' WITH 375 SX CMT. TOC 2280'. PERFS AT 3214-3230 & 6590-6708'. CIBP @ 6500' WITH 4 SX CMT. CIBP @ 3200' WITH 4 SX CMT. CONFIRMED BY COMPANY MAN ON 11/20/01. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1790'. LOAD HOLE WITH MUD. PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 600'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. SDON. 11/21/01: PUMP 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2017' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PERT AT
(TECHNICIAN)

RECEIVED
DEC 07 2001
KCC WICHITA

INVOICED

NOV 28 2001

DATE 12-10-01
INV. NO. 2002061044

NP

Form CC-2/3