

1 030497

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,760-0000

C SW SE, SEC. 15, T 34 S, R 40 (W)EX

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Fermaul "A" Well # 1

Operator: Cities Service Oil & Gas Corp.

County Morton 213.72

Name & Address 3545 NW 58th Street

Well Total Depth 6576 (Marrow) feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 1697

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Johnson Drilling Co., Inc. License Number 7860

Address P. O. Box 659, Evansville, IN 47704

Company to plug at: Hour: 4:00 am Day: 23 Month: August Year: 1985

Plugging proposal received from Bib Gillium

(company name) Cities Service (phone) 405-949-4342
Elevation 3300'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1690'

1st plug to TD with 35 sx cement 4th plug in the Hugoton with 75-100 sx

2nd plug in the Marrow with 50 sx cement 5th plug 30' out of the surface pipe with 50 sx cement

3rd plug in the Toneyka with 75 sx cement 6th plug at 700' with 40 sx cement
solid bridge

7th plug hulls - plug at 40' -- cement to surface with 10 sx cement

9th plug to circulate rat hole with 15 sx, 10th plug to circulate mouse hole with 10 sx
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 am Day: 23 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 6350' with 35 sx cement, 2nd plug at 5600' with 35
sx cement, 3rd plug at 2800' with 100 sx cement, 4th plug at 1768' with 40 sx cement, 5th

plug at 700' with 35 sx cement, 6th & 7th plugs - solid bridge - hulls - plug at 40' --
cement to surface with 10 sx cement, 8th plug to circulate rat hole with 15 sx cement

9th plug to circulate mouse hole with 10 sx cement.

Remarks: Used Class H Cement by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1985

RECEIVED
STATE CORPORATION COMMISSION

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 9811 SEP 24 1985

AUG 28 1985

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: June 21, 1985
month day year

API Number 15- 129-20,760

OPERATOR: License # 5447
Name Cities Service Oil and Gas Corporation
Address 3545 NW 58th Street
City/State/Zip Oklahoma City, OK 73112
Contact Person Raymond Hui
Phone (405) 949-4342

.. C SW SE .. Sec 15 Twp 34 S. Rge 40 East West
(location)
660 .. Ft North from Southeast Corner of Section
1980 .. Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #
Name Not yet known Johnson, H.
City/State Box 659, Eunice, Okla. 47704

Nearest lease or unit boundary line 660 feet.
County Morton
Lease Name Fermaud "A" Well # 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water Est. 606 feet
Lowest usable water formation Pennian
Depth to Bottom of usable water Est. 750 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 1150 feet
Conductor pipe if any required feet
Ground surface elevation Est. 3300 feet MSI
This Authorization Expires 12-14-85
Approved By 6-14-85 R.H. Hui

If (OWWO): old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 6500 feet
Projected Formation at TD St. Louis
Expected Producing Formations St. Louis, Lansing, Morrow

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.D. specifications.

Date 6-13-85 Signature of Operator or Agent Raymond Hui Title Supervisor, Oil & Gas Systems

Spud S-A-55-1, Comp. 20' 30"
Set 1497'

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1985

CONSERVATION DIVISION
Wichita, Kansas