

1 020280

12-31
API NUMBER 15- 189-21,399-00002 34 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. C SW/4, SEC. 36, T 34 S, R 39 W/E
1130 feet from S section line
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Rickart Well # B-1

Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

County Stevens
Well Total Depth 6550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1794

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address English Key Bldg., 333 East English, Suite 215, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 31 Month: 12 Year: 1989

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corporation (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1786'

1st plug at 2790' with 80 sx cement, 2nd plug at 1760' with 50 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

JAN 5 1990
1-5-1990
CONSERVATION DIVISION
Glenn Barlow
(TECHNICIAN)

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8 a.m. Day: 31 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2790' with 80 sx cement,

2nd plug at 1760' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-12-90

Signed Glenn R Barlow (TECHNICIAN)

INV. NO. 26996

FEB 28 1990

MUST BE TYPED
K C-1 12/88

Must be approved by the K.C.C. five (5) days prior to commencing well

Spud Date 12/11/89
month day year

APX C SW Sec 36 Twp 34 S, Rg 39 East West WW

Operator License # 4549
Name: ANADARKO PETROLEUM CORP.
Address: P.O. BOX 351
City/State/Zip: LIBERAL, KS. 67901
Contact Person: JIM BARLOW
Phone: (316) 624-6253

1130 feet from South line of Section
4030 feet from East line of Section
(Note: Locate well on Section Plat Below)

Contractor License #: Calbert Jones
Name: UNKNOWN *

County: STEVENS
Lease Name: RICKART Well #: B-1
Field Name: UNKNOWN

All Drilled For: Well Class: Type Equipment:
Oil ... In] ... Infield XX Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
DWD ... Disposal XX Wildcat ... Cable
Seismic; ... # of Holes

Is this a Prorated Field? ... yes XX no
Target Formation(s): CHESTER
Nearest lease or unit boundary: 1250' 1130'
Ground Surface Elevation: 3286 feet MSL
Domestic well within 330 feet: ... yes XX no
Municipal well within one mile: ... yes XX no
Depth to bottom of fresh water: 550
Depth to bottom of usable water: 620
Surface Pipe by Alternate: XX1 ... 2
Length of Surface Pipe Planned to be set: 1751
Length of Conductor pipe required: *****
Projected Total Depth: 6550
Formation at Total Depth: CHESTER
Water Source for Drilling Operations:
... well ... farm pond XX other

Old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

OWR Permit #:
Will Cores Be Taken?: ... yes XX no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? ... yes XX no
If yes, total depth location:


AS: 1250' FSL; 1250' FULL;
Exp. 6/1/90

AFFIDAVIT

640' Alt. I Req.

PUSHER	<u>Jim Barlow</u>
TD	<u>6550</u> FORMATION <u>ST LOUIS</u>
SURFACE PIPE	<u>1774 @ 878</u>
ANHYDRITE	<u>1786</u> ELEVATION
STARTING TIME & DATE	<u>2 AM 12/11</u>
COMPLETION TIME & DATE	<u>8 AM 12/31</u>
1st PLUG @	<u>2190</u> FT. W/ <u>80</u> SX
2nd PLUG @	<u>1760</u> FT. W/ <u>50</u> SX
3rd PLUG @	<u>700</u> FT. W/ <u>40</u> SX
4th PLUG @	<u>40</u> FT. W/ <u>10</u> SX
RAT HOLE CIRCULATED W/	<u>15</u> SX
MOUSE HOLE CIRCULATED W/	<u>10</u> SX
WATER WELL PLUGGED W/	_____ SX
CEMENT COMPANY	<u>Dowell</u>
TECHNICIAN	<u>G.B.</u>
TYPE OF CEMENT	<u>60/40 676</u>

JAN 5 1990
CONSERVATION DIVISION
Wichita, Kansas
Spud 12-13-89
Set - 8:50 P 17



Mail to:
Rickart
STU
90 2790
80 1760
540 1700
40 60

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or completion;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.

0 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1286.
on of drilling operations? (If plastic liner used,

mb