

5-24-88

382 P

To: 1 110103
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,620-0000

NE SE SE, SEC. 34, T 34 S, R 39 WEX
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9736

Lease Name Lightcap Well # 1

Operator: Dorchester Hugoton, LTD.
Name & Address 9696 Skillman St., Suite 320-LB42
Dallas, TX 75243-8200

County Stevens 107.35
Well Total Depth 3303 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 592

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address P.O. Box 1598, Liberal, KS 67901

Company to plug at: Hour: 2:10 p.m. Day: 24 Month: 5 Year: 19 88

Plugging proposal received from Steve Cruzan

(company name) Dorchester Hugoton, LTD. (phone) 405-338-3594

were: 5 1/2" at 3327' Perfs at 2987-94, 2998-3002, 3135-45, 3170-72, 3178-82, 3200-04, 3206-08,
PBTD 3252' 3214-19'

1st plug pump 4 sx hulls and 250 sx lite cement down 5 1/2",
2nd plug pump 20 sx cement down 8 5/8".

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 24 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 4 sx hulls and 250 sx Howco lite cement down 5 1/2",
2nd plug pumped 20 sx cement down 8 5/8", pressured to 400 lbs.

3rd plug hooked back to 5 1/2" and pumped 30 sx cement, pressured to 700 lbs.

RECEIVED
STATE CORPORATION COMMISSION
6-2-1988
JUN - 2 1988

Remarks: Used light cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

Signed James R. Kapp
(TECHNICIAN)

DATE 6-21-88
INV. NO. 20906